BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PM7/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No. 69

Name of Work:-Improvements to roads Green square Ananthpura in Attur ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Y A Dhanashekar	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no1 9.1,Page no138,PWD SR 2014-15)	Cum	618.00	79.00	Rupees seventy nine only
2	Removing B.S slab of drain and stacking	Sqm	693.00	61.00	Rupees sixty oneonly
3	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	693.00	79.00	Rupees seventy nine only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	297.00	671.00	Rupees six hundred seventy one only
5	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/Kanker/Moorum.KSRRB M100-1 Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	618.00	71.00	Rupees seventy one only
6	Scarifying top bituminious surface dressing or premix carpet including picking up scarified materials,stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges complete as per specifications.	Sqm	624.00	91.00	Rupees ninety one only
7	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no1.3,Page no12,PWD SR 2014-15)	Cum	322.30	1508.00	Rupees one thousand five hundred eigh only

Sl	Description	Unit	Approved Q'ty	Rate Quoted by the Contractor Approved Rates Sri. Y A Dhanashekar	
				Rate	Rate in Words
8	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH Specifications No502 (ITEMNO21.6,Page no157,PWD SR 2014-15)	Sqm	2100.00	36.80	Rupees Thirty six and paise eighty only
9	KSRRB M500-18 Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site,laying with a paver finisher to the required grade,levell and alignment,rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethedesiredcompactionasperMORTHSpecificationclauseno.500completeinallrespectscomplete asperspecifications using100120THcapacityH.M.P with sensor paver grading(35-40mm)with4.5%CRMB55grade(Itemno21.21.1,Pageno16D 2014-15)	Cum	52.50	10658.00	Rupees ten thousand six hundred fifty eight only

Y A Dhanashekar

Signature of the Contractor

Executive Engineer
Yelahanka Division,
BBMP, Bengaluru-64